

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-191-21894-00-00
Spot: E2SESE Sec/Twnshp/Rge: 17-35S-4W
660 feet from S Section Line, 330 feet from E Section Line
Lease Name: DALRYMPLE Well #: 1-A
County: SUMNER Total Vertical Depth: 3840 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>31253</u>	PROD	5.5	3840		300 SX
Op Name: <u>PRIMEXX OPERATING CORPORATION</u>	SURF		250		
Address: <u>4849 GREENVILLE # 1600</u> <u>DALLAS, TX 75206</u>	SURF	8.625	262		200 SX

Well Type: SWD UIC Docket No: D24379.0 Date/Time to Plug: 02/23/2017 8:00 AM
Plug Co. License No.: 8733 Plug Co. Name: DUNKIN, JERRY, INC.
Proposal Rcvd. from: JERRY DUNKIN Company: JERRY DUNKIN Phone: (580) 541-9237

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/23/2017 11:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP WAS SET AT 3450' & CAPPED WITH 2 SKS CEMENT. THE CASING WAS RECOVERED FROM 2220' & PULLED FROM WELLBORE. TUBING WAS RUN TO 953' WHERE 35 SX OF CEMENT WAS SPOTTED. THE TUBING WAS PULLED TO 650' WHERE 35 SX OF CEMENT WAS SPOTTED. THE TUBING WAS PULLED TO 310' WHERE CEMENT WAS CIRCULATED TO SURFACE WITH 110 SKS.

Perfs:

Top	Bot	Thru	Comments
3610	3738		
3547	3594		

Remarks: JERRY DUNKIN CEMENTING WITH COMMON CEMENT

Plugged through: TBG

District: 02

Signed


(TECHNICIAN)

INVOICED

Form CP-2/3

MAR 23 2017

1/8