

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-26174-00-01
Spot: SESESW Sec/Twnshp/Rge: 4-32S-11E
391 feet from S Section Line, 2666 feet from E Section Line
Lease Name: HUDSON Well #: 1
County: CHAUTAUQUA Total Vertical Depth: 2265 feet

Operator License No.: 8736
Op Name: DIXON, JAMES DAVID
Address: 1214 CYCLONE
MOLINE, KS 67353

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2020		
PROD	4.5	2018		125 SX
SURF	8.625	321		170 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/26/2017 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: JAMES D. DIXON Company: _____ Phone: (620) 647-3317

Proposed Plugging Method: 1" to bottom, with gel in hole, spot 10 sacks, pull up 1000 ft, 5 sacks cement, pull up 550 ft and cement to surface.

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/27/2017 12:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1700' gelled hole and spotted 10 sack cement plug. Pulled 1" and perforated casing at 900' and 550'. Ran 1" back into 900' and spotted 10 sack cement. Pulled up to 550' and circulated cement to surface with 170 sacks of cement. Pulled 1" and topped well off. A total of 190 sacks of cement were used to plug this well. Well was cut off and location restored.

Perfs:

Top	Bot	Thru	Comments
1952	1962		

RECEIVED
KCC DIST # 3
MAR 02 2017
CHANUTE, KS
DS
KCC WICHITA
MAR 06 2017

Remarks: WELL WAS PLUGGED DUE TO INACTIVE WELL LIST SENT OT OPERATOR BY KCC.

Plugged through: TBG

District: 03

Signed _____

(TECHNICIAN)

INVOICED
MAR 28 2017

Form CP-2/3