

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-007-20548-00-00  
Spot: NESENWSE Sec/Twnshp/Rge: 7-31S-14W  
1810 feet from S Section Line, 1639 feet from E Section Line  
Lease Name: THUNDERBIRD RANCH Well #: 2-A  
County: BARBER Total Vertical Depth: 4549 feet

Operator License No.: 35216  
Op Name: ENERGYQUEST II, LLC  
Address: 4526 RESEARCH FOREST DR SUITE 200  
THE WOODLANDS, TX 77381

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4540	0	
SURF	8.625	656		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/21/2017 10:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SET CIBP @ 4480'. PERFORATE 4 1/2" CASING AT 680'. RUN TBG INTO 680'. PUMP CMT DOWN TBG FILLING 4 1/2" AND 4 1/2" X 8 5/8" ANNULUS TO SURFACE WITH CMT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/21/2017 2:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

Perfs:

\*\*UNABLE TO GET CIBP PAST 1100' INSIDE OF 4 1/2' CASING DUE TO ROUGH PIPE.\*\* RUN TBG IN TO 4500' & SPOT 200# HULLS & 25 SX CMT. LAY TBG DOWN. PERFORATE 4 1/2" CASING AT 680'. RUN TBG IN TO 680' & PUMPED DOWN TBG WITH 195 SX CMT FILLING 4 1/2" CASING AND 4 1/2" X 8 5/8" ANNULUS TO SURFACE WITH CMT.

Top	Bot	Thru	Comments
4529	4533		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

District: 01

Signed Stephen J. Pfeifer  
(TECHNICIAN)

5A

RECEIVED  
FEB 24 2017  
KCC DODGE CITY

INVOICED  
MAR 28 2017

Form CP-2/3