

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-185-23120-00-01
Spot: W2NENENE Sec/Twnshp/Rge: 10-21S-11W
4981 feet from S Section Line, 365 feet from E Section Line
Lease Name: FAIR B OWWO Well #: 2-10
County: STAFFORD Total Vertical Depth: 3450 feet

Operator License No.: 5056
Op Name: F. G. HOLL COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2970		WITH 2 SX CMT
CIBP		3262		
PROD	5.5	3449	0	WITH 225 SX CMT
SURF	8.625	232		WITH 225 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/24/2017 11:00 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Revd. from: ADAM APLEY Company: F.G. HOLL COMPANY Phone: (620) 793-0915

Proposed Plugging Method: CIBP @ 2970' WITH 2 SX CMT. PERFORATE AT 600'. CIRCULATE CMT TO SURFACE IN & OUT OF 5 1/2".

Plugging Proposal Received By: LARRY HARRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/24/2017 12:55 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 2970' WITH 2 SX CMT. PERFORATED AT 600'. RAN TBG TO 600' & CIRCULATED CMT INSIDE & OUTSIDE OF THE 5 1/2" WITH 185 SX CMT. PULLED TBG & TOPPED OFF WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3353	3356		ARBUCKLE
3339	3344		ARBUCKLE
3018	3024		DOUGLAS SAND

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED COMMON CEMENT BY BASIC ENERGY.

Plugged through: TBG

District: 01

Signed _____

(TECHNICIAN)

RECEIVED
MAR - 2 2017
KCC DODGE CITY

INVOICED
MAR 28 2017

Form CP-2/3