

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-185-11000-00-00
Spot: NWSE Sec/Twnshp/Rge: 30-24S-13W
2031 feet from S Section Line, 2007 feet from E Section Line
Lease Name: HARTER E Well #: 1
County: STAFFORD Total Vertical Depth: 4231 feet

Operator License No.: 3493
Op Name: FISHER, REGINALD D.
Address: 110 N EXCHANGE ST
SAINT JOHN, KS 67576

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4240	2033	WITH 250 SX CMT
SURF	8.625	252		WITH 225 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/06/2017 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: SAND BACK TO 3900' & 5 SX CMT. PUMP 10 SX GEL & 50 SX CMT AT 860'. PUMP 50 SX CMT AT 280'. PUMP 20 SX CMT AT 0-40'.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/06/2017 3:15 PM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

SAND BACK TO 3750' WITH 5 SX CMT ON TOP. 1ST PLUG AT 860' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 280' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 35 SX CMT, TOP OFF WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4160	4166		
4110	4120		
3951	4011		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

District: 01

Signed _____

(TECHNICIAN)

RECEIVED
MAR - 9 2017
KCC DODGE CITY

INVOICED
MAR 28 2017

Form CP-2/3