

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-071-20069-00-00
Spot: NE Sec/Twnshp/Rge: 20-17S-40W
3935 feet from S Section Line, 1320 feet from E Section Line
Lease Name: HUNT Well #: 1
County: GREELEY Total Vertical Depth: 3300 feet

Operator License No.: 4894
Op Name: HORSESHOE OPERATING, INC.
Address: 110 W LOUISIANA STE 200
MIDLAND, TX 79701

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3053	0	WITH 125 SX CMT
SURF	8.625	250		WITH 225 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/15/2017 8:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Revd. from: PHELPS WHITE Company: HORSESHOE OPERATING Phone: (575) 626-7660

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/15/2017 6:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PREVIOUS CASING LEAKS SQUEEZED AT 1855' TO 1915' WITH 175 SX CMT IN 1992 & 1875' WITH 300 SX CMT IN 1983. PUMP 75 SX CMT WITH 300# HULLS AT 2903' THROUGH TBG. FULL CIRCULATION. TAG TOC AFTER 2 HOURS AT 1700'. RAN CBL FROM 1700' TO 15'. HAD GOOD CMT FROM 1700' TO 1450' THEN SCATTERED CMT STRINGERS AS HIGH AS 1050'. RUN TBG TO 1632' & SPOT 40 SX CMT FROM 1632' TO 1000'. PERFORATE 3 HOLES AT 300'. RUN TBG TO 800'. CIRCULATE CMT TO SURFACE INSIDE THE 4 1/2" WITH 50 SX CMT. ATTEMPT TO CIRCULATE CMT UP THE 4 1/2" X 8 5/8" ANNULUS THROUGH THE PERFS AT 300'. PUMPED 200 SX CMT (150 SX OVER CAPACITY & LOST CIRCULATION). WAIT ON MORE CMT AFTER 3 HOURS. TOP OFF 4 1/2" WITH 20 SX CMT & PUMP 200# HULLS & 80 SX CMT DOWN THE 4 1/2" X 8 5/8" ANNULUS. STAYED FULL.

Perfs:


Top	Bot	Thru	Comments
2936	2997		

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED
FEB 23 2017
KCC DODGE CITY

INVOICED
MAR 28 2017

Form CP-2/3