

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-22144-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 10-7S-19W
330 feet from S Section Line, 2310 feet from E Section Line
Lease Name: JACKSON Well #: 2
County: ROOKS Total Vertical Depth: 3468 feet

Operator License No.: 34903
Op Name: JASPAR CO.
Address: 1681 LIMESTONE ROAD SOUTH PO B
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3400		175 SX
SURF	8.625	258		130 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/15/2017 1:45 PM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: SHANE VEHIGE Company: JASPAR CO. DBA Phone: (785) 623-6982

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/400 # hulls.
Casing leak at 2095' - 2300'.
1520' w/125 sx cement, 780' w/265 sx cement, 630' cwc w/150 sx cement.
Production perforations: 3164' - 3436'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/15/2017 3:45 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3200' and pumped 100 sx cement w/100 # hulls. Pulled tubing to 1985' and pumped 75 sx cement w/50 # hulls. Pulled tubing to 900' and pumped 120 sx cement to circulate cement to surface. Pulled all tubing and topped off 4 1/2" casing with 15 sx cement. Visually checked 8 5/8" x 4 1/2" annulus and cement was to surface.

GPS: 39.45288N -099.42460W

Perfs:

Top	Bot	Thru	Comments
3436	3436		
3372	3372		
3370	3372		
3351	3351		
3350	3350		
3348	3353		
3329	3329		
3328	3330		
3274	3274		
3273	3275		
3261	3261		
3260	3264		
3235	3235		
3234	3236		
3178	3178		
3164	3164		

Remarks: QUALITY OILWELL CEMENTING TICKET # 005

Plugged through: TBG

District: 04

Signed _____

Pat Bedore
(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

MAR 13 2017

CONSERVATION DIVISION
WICHITA, KS

FEB 23 2017

Form CP-2/3

INVOICED
MAR 28 2017