

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-067-20263-00-00  
Spot: NENENWSW Sec/Twnshp/Rge: 33-27S-37W  
2594 feet from S Section Line, 4141 feet from E Section Line  
Lease Name: REDINGER GU-B Well #: 2  
County: GRANT Total Vertical Depth: 2801 feet

Operator License No.: 33999  
Op Name: LINN OPERATING, INC.  
Address: 600 TRAVIS STE 5100  
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2801	0	WITH 800 SX CMT
SURF	8.625	701		WITH 385 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/01/2017 10:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: JASON PHELPS Company: LINN OPERATING Phone: (281) 840-4000

Proposed Plugging Method: ESTIMATED TOF @ 2600'. RTIH TO TOF & SPOT 100 SX CMT. PULL UP HOLE TO 1300' & WOC. SPOT 35 SX CMT AT 1300'. WOC. PULL UP TO 730' & CIRCULATE CMT TO SURFACE. CHECK BACKSIDE WITH CMT TO 500 PSI.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/01/2017 1:30 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

TOP OF FILL AT 1848'. PUMP 65 SX CMT WITH 200# HULLS AT 1848' & HAD GOOD CIRCULATION THE WHOLE TIME. BROKE OFF & HOLE STADING FULL. PULL TBG UP TO 746' & PUMP LESS THAN 1 BBL WATER BEFORE IT LOADED. PUMPED 75 SX CMT FROM 0' TO 746'. PULLED TBG OUT OF HOLE & TOPPED OFF WITH 10 SX CMT. TIED ONTO BACKSIDE & PRESSURED UP TO 500 PSI. WOULDN'T TAKE ANY CMT.

Perfs:

Top	Bot	Thru	Comments
2657	2776		

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA HIGH FL\*\* USED COMMON CEMENT BY QUALITY WELL SERVICE.

Plugged through: TBG

District: 01

Signed

*Kenny Sullivan*

(TECHNICIAN)

INVOICED

MAR 28 2017 Form CP-2/3

RECEIVED  
MAR - 6 2017  
KCC DODGE CITY

*MS*

579