

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-081-00552-00-00
Spot: NENESW Sec/Twnshp/Rge: 23-30S-34W
2326 feet from S Section Line, 2968 feet from E Section Line
Lease Name: ANTON Well #: 1
County: HASKELL Total Vertical Depth: 2730 feet

Operator License No.: 33988
Op Name: LEBOSQUET GAS OPERATIONS, LLC
Address: 535 S EMPORIA STE 103
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	2510	0	WITH 800 SX CMT
SURF	10.75	648		WITH 350 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/23/2017 8:30 AM
Plug Co. License No.: 34199 Plug Co. Name: RAWHIDE WELL SERVICE, LLC
Proposal Rcvd. from: STEVE HELM Company: LEBOSQUET GAS OPERATIONS Phone: (316) 264-6722

Proposed Plugging Method: PUMP 50 SX CMT & 100# HULLS AT 1200'. PRESSURE TEST CASING TO 500 PSI. PERFORATE AT 670'. PUMP 75 SX CMT AT 670' WITH 50# HULLS IN LAST 30 SX CMT. PLUG FROM 350' TO 0'.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/23/2017 3:30 PM KCC Agent: WADE KLAUS

Actual Plugging Report:

2/23/17: 1ST PLUG AT 1069' WITH 50 SX CMT & 150# HULLS. PERFORATE AT 665'.
2ND PLUG AT 640' WITH 75 SX CMT. 50# HULLS IN LAST 30 SX CMT. PERFORATE AT 355'. PUMPED 175 SX CMT. LOST CIRCULATION. 2/24/17: TAGGED TOC @ 15' INSIDE & OUTSIDE OF CASING. TOPPED OFF WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2510	2730	CSG	

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC.

Plugged through: TBG

District: 01

Signed [Signature]

(TECHNICIAN)

RECEIVED
MAR - 2 2017
KCC DODGE CITY [Signature]

INVOICED Form CP-2/3
MAR 28 2017