

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-063-22251-00-00  
Spot: SWSESENW Sec/Twnshp/Rge: 13-13S-29W  
2395 feet from N Section Line, 2220 feet from W Section Line  
Lease Name: ULTRA UNIT Well #: 1-13  
County: GOVE Total Vertical Depth: 4621 feet

Operator License No.: 6039  
Op Name: L. D. DRILLING, INC.  
Address: 7 SW 26TH AVE  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4618		500 SX
SURF	8.625	387		300 SX
T1	2.375	4589		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/28/2017 8:00 AM  
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC  
Proposal Rcvd. from: MIKE KASSELMAN Company: L. D. DRILLING, INC. Phone: (620) 793-3051

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 16 sx gel and 600 # hulls.  
~~Circulated cement in casing from top to bottom.~~  
Perforations: 4159' - 4161', 4167' - 4169', 4182' - 4185' and 4300' - 4303'  
*Production casing cemented top to bottom w/500 sx.*

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/28/2017 1:15 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 4251' and pumped 16 sx gel followed by 75 sx cement w/250 # hulls. Pulled tubing to 2350' and pumped 100 sx cement. Pulled tubing to 1425' and pumped 170 sx cement. Good circulation of cement. Pulled tubing out. Topped off casing with 15 sx cement. Tied on to backside and squeezed with no cement. Shut in pressure 400 psi.

GPS: 38.92400 -100.49333

Perfs:


Top	Bot	Thru	Comments
4300	4303		
4182	4185		
4167	4169		
4159	4161		

Remarks: BASIC CEMENTING TICKET # 9988A

Plugged through: TBG

District: 04

Signed

  
(TECHNICIAN)

CM

MAR 03 2017

Received  
KANSAS CORPORATION COMMISSION

MAR 13 2017

CONSERVATION DIVISION  
WICHITA, KS

INVOICED  
MAR 28 2017

Form CP-2/3