

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-167-20435-00-00  
Spot: W2SESENE Sec/Twnshp/Rge: 8-14S-14W  
2981 feet from S Section Line, 554 feet from E Section Line  
Lease Name: R J ANSCHUTZ TWIN Well #: 1  
County: RUSSELL Total Vertical Depth: 2560 feet

Operator License No.: 30737  
Op Name: M.A. YOST OPERATIONS, INC  
Address: 30 N BROOKS PO BOX 811  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2559		
SURF	8.625	196		140 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/15/2017 8:30 AM  
Plug Co. License No.: 34275 Plug Co. Name: SCOTT SERVICES LLC  
Proposal Rcvd. from: JACK YOST Company: M.A. YOST OPERATIONS, INC DBA Phone: (785) 483-0271

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/300 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/15/2017 12:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 900', 480' and 200'. Ran tubing to 2400' and pumped 125 sx cement w/50 # hulls mixed in. Pulled tubing to 1200' and pumped 110 sx cement w/50 # hulls. Cement circulated to the pit. POOH. Pumped 15 sx cement and topped off casing. Braden head was filled with 5 sx cement.

GPS: 38.85075 -098.89341

Perfs:

Remarks: GLOBAL CEMENTING

Plugged through: TBG

District: 04

Signed

*Ray Dinkel*

(TECHNICIAN)

CM

Received  
KANSAS CORPORATION COMMISSION

MAR 13 2017

CONSERVATION DIVISION  
WICHITA, KS

INVOICED  
MAR 28 2017

Form CP-2/3

FEB 23 2017