

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-153-20709-00-00
Spot: SWSENE Sec/Twnshp/Rge: 24-1S-33W
2970 feet from S Section Line, 990 feet from E Section Line
Lease Name: HOLTHUS Well #: 1
County: RAWLINS Total Vertical Depth: 4350 feet

Operator License No.: 31389
Op Name: NOBLE PETROLEUM, INC.
Address: 8918 W. 21ST ST. N. SUITE 200 #304
WICHITA, KS 67205

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4349		450 sx
SURF	8.625	312		170 sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/24/2017 8:00 AM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: JOHNNIE RILEY Company: HURRICANE SERVICES, INC. Phone: (316) 303-9515

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/800 # hulls.
8 5/8" surface casing set at 312 w/170 sx cement.
4 1/2" production casing set at 4349' w/450 sx cement.
TD 4350'. No two stage cementing.
Perforations: 4255', 4238', 4231', 4190', 4163', 4145', 4088', 4070', 4051', 4087' - 4090', 4063' - 4072', 4049' - 4052'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/24/2017 8:00 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated 2 holes each in production casing at 2875' and 2164'. Ran tubing to 4000'. Hurricane Services pumped 100 sx cement w/300 # hulls. Pulled tubing to 2800' and pumped 100 sx cement w/300 # hulls. Pulled tubing to 1400' and pumped 80 sx cement w/150 # hulls. Cement circulated. PTOH. Topped off 4 1/2" casing with 35 sx cement. Hooked to backside and pumped 20 sx cement. Maximum pressure 275 psi. Blew a hole in 8 5/8" surface casing.

Perfs:

Top	Bot	Thru	Comments
4231			
4145	4163		
4088			
4087	4090		
4070			
4063	4072		
4051	4255		OA
4049	4052		

Remarks: HURRICANE SERVICES TICKET # 50965

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

MAR 9 7 2017

MAR 13

CONSERVATION DIVISION
WICHITA, KS

INVOICED

MAR 28 2017

Form CP-2/3