

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-057-20848-00-00
Spot: NWSWNE Sec/Twnshp/Rge: 25-26S-23W
1798 feet from S Section Line, 1547 feet from W Section Line
Lease Name: NAU 25C Well #: ↓
County: FORD Total Vertical Depth: 5090 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4920		
PC		1425		CEMENTED WITH 225 SX CMT. 20 SX CMT CIRCULATED TO PIT
PROD	5.5	5078	0	WITH 175 SX CMT
SURF	8.625	372		WITH 225 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/27/2017 9:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: SCOTT BOEH Company: RITCHIE EXPLORATION Phone: (620) 617-4671

Proposed Plugging Method: HAS CIBP @ 4920'. TAG & TOP WITH 2 SX CMT. PERFORATE AT 1520' & PUMP 50 SX CMT IN & OUT WITH 100# HULLS IN LAST HALF. PERFORATE AT 875' & CIRCULATE TO SURFACE.

Plugging Proposal Received By: LARRY HARRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/27/2017 12:15 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

TAGGED CIBP @ 4922'. PULLED TBG UP TO 4919' & SPOTTED 10 SX CMT ON TOP OF CIBP. PULLED TBG TO 1537' & CIRCULATED CMT TO SURFACE WITH 155 SX CMT PLUS 200# HULLS. PRESSURED THE BACKSIDE TO 200# WITH 20 SX CMT. PULLED TBG & TOPPED OFF WITH 25 SX CMT.


Top	Bot	Thru	Comments
4974	4975		
4927	4930		

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

District: 01

Signed 

RECEIVED
MAR - 2 2017
KCC DODGE CITY 

(TECHNICIAN) INVOICED
MAR 28 2017

Form CP-2/3