

To: 1 090046
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION App.
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

1-22
API NUMBER 15- 097-21,109-0000 201R
SW NE, SEC. 9, T 28 S, R 16 W/4E

TECHNICIAN'S PLUGGING REPORT

Operator License # 6892
Operator: Trisch Production
Name & Address P.O. Box 1408
Longview, TX 75606

3300 feet from S section line
2164 feet from E section line
Lease Name Day Well # 1
County Kiowa 157.62
Well Total Depth 4850 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 464

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service Inc. License Number 5893

Address P.O. Box 847, Pratt, KS 67124-0847

Company to plug at: Hour: 9:30 a.m. Day: 22 Month: 1 Year: 19 91

Plugging proposal received from Bruce Wagner

(company name) Pratt Well Service Inc. (phone) 316-672-2531

were: 4 1/2" at 4849' w/125 sx cement, PBTD 4728', Perfs at 4662-63'
1st plug sand back to 4510' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10 a.m. Day: 22 Month: 1 Year: 1991

ACTUAL PLUGGING REPORT 1st plug sanded back to 4510' and dumped 4 sx cement on top of sand through bailer.
2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,
released 8 5/8" wiper plug and pumped 150 sx cement.
Maximum pressure 800 psi and shut in 450 psi. 1-31-91

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Rec' 2520'
(if additional description is necessary, use BACK of this form.)

INVOICED
I hereby acknowledge and observe this plugging.

DATE FEB 14 1991
INV. NO. 30740

Signed [Signature]
(TECHNICIAN)