

To: 1121033 5-19
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-21,154-0000

SW SE NE, SEC. 14, T 22 S, R 14 W/E
2970 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30395
Operator: Iannitti Oil Company
Name & Address: P.O. Box 308
Great Bend, KS 67530

Lease Name Marmie A Well # 1
County Stafford 123.18
Well Total Depth 3790 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 275

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529
Address: P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 11:30 a.m. Day: 19 Month: 5 Year: 19 95

Plugging proposal received from Dick Iannitti

(company name) Iannitti Oil Company (phone) 316-792-2921

were: 5 1/2" at 3787' w/125 sx cement, PBSD 3787'; Perfs at 3782-85'
1st plug sand back to 3730' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:30 p.m. Day: 19 Month: 5 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug sanded back to 3730' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped in 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Pumping pressure 0-200 psi and shut in 50 psi.

RECEIVED STATE CORPORATION COMMISSION
MAY 26 1995
5-26-95

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2200' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE JUN 13 1995
INV. NO. 42954

Signed Steve Pfeifer (TECHNICIAN)