

To: 121032 5-19
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-21,972-0000

NE SE NE, SEC. 14, T 22 S, R 14 W/E
3630 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30395
Operator: Iannitti Oil Company
Name & Address: P.O. Box 308
Great Bend, KS 67530-0308

Lease Name Marmie A Well # 2
County Stafford 122.20
Well Total Depth 3760 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 252

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529
Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 9:30 a.m. Day: 19 Month: 5 Year: 1995

Plugging proposal received from Dick Iannitti
(company name) Iannitti Oil Co. (phone) 316-792-2921

work: 5 1/2" at 3756' w/150 sx cement, Perfs at 3591-94, 3568-71, 3551-54, 3512-14, 3476-78, 3454-56'
1st plug sand back to 3400' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30 a.m. Day: 19 Month: 5 Year: 1995

ACTUAL PLUGGING REPORT 1st plug sanded back to 3400' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped in 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Pumping pressure 0-600 psi and shut in 100 psi. 5-26-95 MAY 26 1995

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2100' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE JUN 13 1995
42955

Signed Duane Rumbin
(TECHNICIAN)