

To: 1-120391
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

4-2
API NUMBER 15- 185-22,309-0000
SE NE NE, SEC. 14, T 22 S, R 14 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 6588
Operator: Woodman-Iannitti Oil Company
Name & Address: Box 308
Great Bend, KS 67530

4290 feet from S section line
330 feet from E section line
Lease Name Marmie Well # 3
County Stafford 122.95
Well Total Depth 3783 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 303

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635
Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 2 p.m. Day: 2 Month: 4 Year: 19 90

Plugging proposal received from Gary Burke
(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 5 1/2" at 3771' w/125 sx cement Open hole 3771-3783'
1st plug sand back to 3720' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 3:30 p.m. Day: 2 Month: 4 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3720' and dumped 5 sx cement on top of sand through bailer,
2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug, and pumped 100 sx cement.

Pumping pressure 0-500 psi and shut in 250 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 1924' of 5 1/2" casing.

(additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-18-90
INV. NO. 27880

APR 06 1990
4-6-90
CONSERVATION DIVISION
Wichita, Kansas

Signed Duane Rankin (TECHNICIAN)