

1 120562

4-30 15-185-10935-0000 49 R
API NUMBER 15- Drill Completion Date 10/19/51

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW NW SW, SEC. 13, T. 22 S, R. 14 W/E
1650 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

*Rec'd
5-8-91*

Operator License # 30457

Lease Name Thayer Well # 1

Operator: T-Bar Exploration Inc.

County Stafford 122.68

Name & Address 206 Wellington

Well Total Depth 3775 feet

Enid, OK 73703

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 400

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9 a.m. Day: 30 Month: 4 Year: 19 91

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 3768', Perfs at 3171-3637' (5 sets)

1st plug sand back to 3120' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 35 sx cement, 10 sx gel, release wiper plug and pump 100 sx cement,

3rd plug pump in 8 5/8" X 5 1/2" annulus with 100 sx cement.

5 1/2" casing shot at 800' and at 2400'.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11 a.m. Day: 30 Month: 4 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3120' and dumped 5 sx cement

on top of sand through bailer,

2nd plug pumped into 5 1/2" casing with 35 sx cement, 10 sx gel with hulls mixed in,

release 5 1/2" wiper plug and pumped 100 sx cement. Pumping pressure 0-500 psi, shut in 300 psi.

3rd plug pumped in 8 5/8" X 5 1/2" annulus with 5 sx cement. Shut in 900 psi.

Operator stated that Phillips Petroleum's record stated that the 5 1/2" was squeezed at 700'.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.

(if additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Duane Rankin (TECHNICIAN)

DATE 5-16-91

INV. NO. 31821