

To: 041304
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202
TECHNICIAN'S PLUGGING REPORT

4-17 API NUMBER 15-185-22073-0000
NWNW5N SEC. 13, T. 22 S, R. 14 W/4
2310 feet from (S) section line
4950 feet from (E) section line

Operator License / 0001
Operator: KCC (Fee Fund) Dist. #1
Name & Address: 304 W. McArthur
Dodge City, KS. 67801
(control # 980039-001)

Lease Name Thayer Well # 3
County Stafford
Well Total Depth 3850 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8" feet 386

Abandoned Oil Well Gas Well _____ Input Well _____ SYD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Mikes Testing & Salvage, Inc. License Number 31529
Address South Main, P.O. Box 209, Chase, KS. 67524-0209
Company to plug at: Hour: 12:30 P.M Day: 17 Month: 4 Year: 1998

Plugging proposal received from Manny Boatwright
(company name) Mikes Testing & Salvage, Inc. (phone) 316-938-2943

work: 5 1/2" casing @ 3849' w/220 sx. cement; Hole bridged off @ 3300'; Perfs @ 3800-02'
1st plug sand back to 3250' + dump 5sx. cement on top of sand bridge through bailer.
2nd plug spot 50 sx. cmt. @ 800'
3rd plug spot 50 sx. cmt. @ 400'
4th plug spot 10 sx. cmt. @ 40'

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 1:45 P.M Day: 17 Month: 4 Year: 1998

ACTUAL PLUGGING REPORT 1st plug sanded back to 3200' + dumped 5sx. cement on top of sand bridge through bailer,

Spotted cement plugs through 5 1/2" casing:
2nd plug loaded hole w/gel + spotted 50 sx. cement @ 800',
3rd plug spotted 50 sx. cement @ 400',
4th plug spotted 10 sx. cement @ 40', Tapped well off w/10 sx. cement.

Remarks: Used 60/40 poz mix 6" gel by Allied. Recovered 1824' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.
Signed Stephen J. Puffer (TECHNICIAN)
FORM CP-2/3