

1 120640

10-10 15-185.10932-0000

80R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drilled 5/4/52

SE SW NW, SEC. 13, T 22 S, R 14 W/E

2970 feet from S section line

4290 feet from E section line

Lease Name McMillan Well # A-1

County Stafford 123.01

Well Total Depth 3785 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 375

TECHNICIAN'S PLUGGING REPORT

Operator License # 5229

Operator: Phillips Petroleum Company

Name & Address Rt. 3, Box 20-A

Great Bend, KS 67530

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1 p.m. Day: 10 Month: 10 Year: 19 91

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" casing @ 3775' w/150 sx cement, PBSD 3694', Perfs at 3636-42',

Hole in 5 1/2" at 2327-90', squeezed with 100 sx cement, at 303-18', squeezed with 150 sx cement

1st plug run tubing to 3630' and pump 100 lbs. hulls, pull up to 3550' and pump 40 sx cement

with hulls, 2nd plug pull tubing to 3350' and pump 22 sx gel, pull tubing, perforate at

850' and run tubing back to 850', circulate cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 8 p.m. Day: 10 Month: 10 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug ran tubing to 3651' and pumped 100 lbs. hulls, tubing to 3532' and pumped 40 sx cement,

2nd plug tubing to 3344' and pumped 22 sx gel, pulled all tubing and shot casing at 530',

ran tubing back to 850' and circulated with 100 sx cement,

3rd plug pulled all tubing and pumped in 5 1/2" casing with 25 sx cement.

Pumping pressure 0-800 psi and shut in 300 psi. The valves in braden head were full of cement.

Remarks: Used 60/40 Pozmix 6% gel by (RECEIVED) No casing recovery.

INVOICED (if additional description is necessary, use BACK of this form.)

DATE 11-14-91 (did / observe this plugging, OCT 15 1991)

INV. NO. 33714

Signed Duane Rankin (TECHNICIAN)

10-15-91