

1052222

TO: 2-4 API NUMBER 15-Drilled 1952

STATE CORPORATION COMMISSION N/2 SE NW, SEC. 13, T 22 S, R 14 W

CONSERVATION DIVISION - PLUGGING SECTION 3630 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 3300 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME Rita WELL # 2

TECHNICIAN'S PLUGGING REPORT COUNTY Stafford 123.18

OPERATOR LICENSE # 32017 WELL TOTAL DEPTH 3790 FEET

OPERATOR: ABC Oil & Salvage PRODUCTION CSG: SIZE 5 1/2" FEET 3775

NAME AND RR #3, Box 151 SURFACE CASING: SIZE 8 5/8" FEET 383

ADDRESS Lyons, KS 67554

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR Quality Well Service, Inc. LICENSE NUMBER 31925

ADDRESS 249 Beth Dr., Sterling, KS

COMPANY TO PLUG AT: HOUR: 10 a.m. DAY: 4 MONTH: 2 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM Richard McIntyre

(COMPANY NAME) Quality Well Service, Inc. (PHONE) 316-727-3410

WERE: Perfs at 3466-68, 3476-78, 3634-36, 3694-96'

1st plug sand back to 3396' and dump 5 sx cement on top of sand through bailer,

2nd plug at 900' w/10 sx gel and 50 sx cement,

3rd plug at 413' with 50 sx cement,

4th plug at 40' with 10 sx cement.

PLUGGING PROPOSAL RECEIVED BY Richard Lacey

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 2:30 p.m. DAY: 4 MONTH: 2 YEAR: 1998

ACTUAL PLUGGING REPORT 1st plug sanded back to 3396' and dumped 5 sx cement on top of sand through bailer,

Pumped plugs through casing:

2nd plug at 900' with 10 sx gel and 50 sx cement displaced with 5 sx gel,

3rd plug at 413' with 50 sx cement,

4th plug at 40' with 10 sx cement.

REMARKS: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 1920' of 5 1/2" casing.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

DATE FEB 17 1998

SIGNED Richard M. Lacey
(TECHNICIAN) FORM CP-2/3

INV. NO. 50081

2-4

FEB 10 1998 2-10-98
CONVENT
Wichita, Kansas