

To: 1 120642
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

10-14 15.185-12872-0000 137
API NUMBER 15- Drill Completion Date 12/29/53

W/2 NW NW, SEC. 13, T 22 S, R 14 W/2
4620 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5229

Lease Name McMillan Well # A-4

Operator: Phillips Petroleum Company

County Stafford 122.36

Name:

Well Total Depth 3765 feet

Address Rt. 3 Box 20-A

Conductor Pipe: Size _____ feet

Great Bend, KS 67530

Surface Casing: Size 10 3/4 feet 371

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9 a.m. Day: 14 Month: 10 Year: 19 91

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 7" at 3750' w/200 sx cement, Open hole 3750-65'

1st plug sand 7" casing back to 3700' and dump 7 sx cement on top of sand through bailer,

2nd plug pump in 10 3/4" surface casing with 400 lbs. hulls, 12 sx gel, 75 sx cement,

12 sx gel, 200 lbs. hulls and 150 sx cement.

RECEIVED

STATE CORPORATION COMMISSION

10-22-91
Plugging Proposal Received by Duane Rankin OCT 22 1991
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Wichita, Kansas

Operations Completed: Hour: 5:30 p.m. Day: 14 Month: 10 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded 7" casing back to 3700' and dumped 7 sx cement
on top of sand through bailer,

2nd plug pumped into 10 3/4" surface casing with 400 lbs. hulls, circulated on backside
of 10 3/4",

3rd plug ran tubing to 906' and pumped 2 sx gel and 75 sx cement,

4th plug pulled tubing to 656' and pumped 15 sx gel, pulled tubing to 406' and pumped

150 sx cement, cement did circulate.

Remarks Used 60/40 Pozmix 6% gel by Allied. Recovered 1830' of 7" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

(old, xxxxxx) observe this plugging.

DATE 11-14-91

Signed Duane Rankin
(TECHNICIAN)

INV. NO. 33715