

10-24

15-145-00889-0000

To: 1 120490
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Drill Completion Date 6/25/53

NE NW NW, SEC. 27, T 22 S, R 15 W
4950 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5163

Lease Name Sutton Well # 2
County Pawnee 128.79

Operator: White Hawk Oil Company
Name & Address P.O. Box 1150
Great Bend, KS 67530

Well Total Depth 3963 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 220

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Chase Well Service, Inc. License Number 6123

Address P.O. Box 355, Great Bend, KS 67530

Company to plug at: Hour: 10 a.m. Day: 24 Month: 10 Year: 19 90

Plugging proposal received from Robert E. Lundberg

(company name) White Hawk Oil Company (phone) 913-254-7855

were: 5 1/2" at 3962' w/150 sx cement, Perfs at 3947-57', Top of tubing fish at 890', top of rod fish 1075'
1st plug recover tubing to Anhydrite, 940', perforate 5 1/2" casing at 890', run tubing to 940' and circulate cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1 p.m. Day: 24 Month: 10 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug cleaned hole to 890', perforated 5 1/2" casing at 888-89' with 3 shots 3/4", ran tubing to 890' and pumped in 150 sx cement, 5 1/2" casing circulated, 2nd plug pulled all tubing and squeezed 5 1/2" casing with 50 additional sx cement. No pressure.

3rd plug pumped between 5 1/2" X 8 5/8" annulus with 160 sx cement. No pressure. Not on vacuum.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.

(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

OCT 31 1990

Signed [Signature] (TECHNICIAN)

DATE 11-6-90

INT. NO. 2985-9

10-31-90

10-24