

15-185-01619-00-01

To: 1. 052206  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION App.  
130 S. Market, Room 207B  
Wichita, KS 67202

12-15

API NUMBER 15- Drilled 4/22/42

TECHNICIAN'S PLUGGING REPORT

Operator License / 3911  
Operator: RAMA Operating Co., Inc.  
Name:  
Address: P.O. Box 159  
Stafford, KS 67578

NW SW NW, SEC. 27, T 23 S, R 12 W/E  
App. 3630 feet from S section line  
App. 4950 feet from E section line  
Lease Name H. Meyer Well # 1  
County Stafford 124.74  
Well Total Depth 3838 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 375

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529  
Address P.O. Box 467, Chase, KS 67524

Company to plug at: Hour: 3 P.m. Day: 15 Month: 12 Year: 19 97

Plugging proposal received from James Ray

(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

were: 5 1/2" at 3818', Open hole 3818-3838'

1st plug sand back to 3670' and dump 5 sx cement on top of sand through bailer,

2nd plug at 700' with 50 sx cement,

3rd plug at 400' with 50 sx cement,

4th plug at 40' with 10 sx cement.

12-18-97

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 4:45 p.m. Day: 15 Month: 12 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 3670' and dumped 5 sx cement on top of sand through bailer,

Pumped plugs through casing:

2nd plug at 700' with 50 sx cement,

3rd plug at 400' with 50 sx cement,

4th plug at 40' with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1787' of 5 1/2" casing.  
If additional description is necessary, use BACK of this form.)

INVOICED

I (did ~~XXXXXX~~ observe this plugging.

DATE JAN 06 1998

INV. NO. 49839

Signed Richard W. Lacey (TECHNICIAN)