

To: 1 052151 8-4
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-Comp.1/23/64 15-185-19377-0000
N/2 SE SE, SEC. 28, T 23 S, R 12 W/8

TECHNICIAN'S PLUGGING REPORT

Operator License # 3911

Operator: RAMA Operating Co., Inc.
Name & Address P.O. Box 159
Stafford, KS 67578

990 feet from S section line
660 feet from E section line

Lease Name H. Knoche Well # 1
County Stafford 125,00

Well Total Depth 3846 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 200

Abandoned Oil Well Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementing Co. License Number

Address

Company to plug at: Hour: 8:30 a.m. Day: 4 Month: 8 Year: 19 97

Plugging proposal received from Robert Austin

(company name) RAMA Operating Co., Inc. (phone) 316-234-5191

logs: 5 1/2" at 3843', Open hole 3843-46'

1st plug pump 2 sx hulls and 35 sx cement,

2nd plug pump 25 sx cement at 900',

3rd plug circulate cement to surface from 530'.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:45 p.m. Day: 4 Month: 8 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug ran tubing to 3500' and pumped 50 sx cement. Waited on cement two hours, tagged cement at 3022',

2nd plug pulled tubing to 900' and pumped 25 sx cement,

3rd plug pulled tubing to 540', circulating cement to surface.

Pulled tubing and topped off.

Casing cemented from 500-0'.

Remarks: Used 60/40 Pozmix 6% gel 3% cc by Allied. No casing recovery.

(If additional description is necessary, use BACK of this form.)

I (holder) hereby observe this plugging.

DATE 8-14-97

INV. NO. 488000

8-4

Signed Richard W. Lacey
(TECHNICIAN)

8-12-97
RECEIVED
STATE CORPORATION COMMISSION
WICHITA, KANSAS
AUG 22 11 43 AM '97