

1 080384

Docket No. D-17,048

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-20,292 -00-01

NE SE NW, SEC. 28, T 23 S, R 12 W/E

3630 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6886

Lease Name Meyer B Well # 1

Operator: Robert L. Austin

County Stafford 128.70

Name & Address: Box 159

Well Total Depth 3960 feet

Stafford, KS 67578

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 226

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well X D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Services License Number _____

Address Box 579, Great Bend, KS 67530

Company to plug at: Hour: 9:30 am Day: 3 Month: June Year: 19 85

Plugging proposal received from Robert L. Austin

(company name) Robert L. Austin (phone) 316-234-5191

were: 5 1/2" at 3835' Open Hole from 3835-2960'

Spotted 50 sx cement with 1/4 pound flow seal and 4% cc at 1860'. Waited 2 hours and 30

minutes and tagged cement at 1790'. Pulled tubing to 1060'. Spotted 100 sx cement.

Waited 2 hours and 30 minutes. Tagged cement at 1120'. Pulled tubing to 750'.

Spotted 50 sx cement and 2 sx hulls. Pulled tubing to 480'. Spotted 50 sx cement and 1

Plugging Proposal Received by J. R. Murphy (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 12:45 pm Day: 4 Month: June Year: 19 85

ACTUAL PLUGGING REPORT sack hulls. Shut well in over night. Tagged cement at 555'

on 5-4-85 at 9:00 am. Pulled tubing to 410'. Spotted 100 sx cement. Broke circulation

and pulled tubing to 250'. Spotted 50 sx cement. Pumped 50 sx cement

Layed tubing down. Filled 5 1/2" with 5 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
6-17-85
JUN 17 1985

Used 455 sx cement.

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 50/50 Pozmix 3% cc by Halliburton NO Rec.

(additional description is necessary, use BACK of this form.)

INVOICED

I (did / ~~did not~~) observe this plugging.

DATE 6-19-85

Signed J. R. Murphy (TECHNICIAN)

INV. NO. 8578