

1 080457

Docket No. D-19,134

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- NA 15-185-01622-0001

NW NW NE, SEC. 28, T 23 S, R 12 W/E

4950 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6981

Lease Name Meyer Well # 1

Operator: Gas Marketing, Inc.

County Stafford

Name & Address P. O. Box 159

Well Total Depth 3830 124.48 feet

Stafford, KS 67578

Conductor Pipe: Size _____ feet

Surface Casing: Size 9 5/8 feet 270

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well X D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Services License Number _____

Address P. O. Box 963, Pratt, KS 67124

Company to plug at: Hour: 1:00 pm Day: 16 Month: December Year: 19 85

Plugging proposal received from Bob Austin

(company name) Gas Marketing (phone) 316-234-5191

were: 5 1/2" at 3828' PBTD 3150' Perfs at 2950-3110'

1st plug set 5 1/2" bridge plug at 3150' with 1 sack calceal

2nd plug pull tubing to 600' and squeeze well with 150 sx cement.

Plugging Proposal Received by J. H. Metz
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 2:00 pm Day: 16 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 5 1/2" bridge plug set at 3150' with one sack calceal,

2nd plug pulled tubing to 600' and squeezed well with 150 sx cement.

Maximum pressure 400 psi and shut in 50 psi. Well was squeezed at 495'. Cement circulated in cellar - 9 5/8" full.

Remarks: No recovery. Used 50/50 Pozmix 2% gel. by Halliburton
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE DEC 27 1985
INV. NO. 11738

observe this plugging.
12-27-85 SIGNATURE
Signed J. H. Metz
(TECHNICIAN)
DEC 27 1985