

1060360

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-22.093 - 0000

C S/2 NE , SEC. 29 , T 23 S, R 12 W/EX
3300 feet from ^N SE Corner of ~~W/SX~~ section line
1320 feet from ^W SE Corner of ~~W/EX~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9196

Lease Name Rice Well # 1

Operator: West Trail Exploration Co.

County Stafford

Name & Address 1531 Stout Street # 530

Well Total Depth 3907 126.98 feet

Denver, CO 80202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 311

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Cougar Drilling Co. License Number 5138

Address 555 North Woodlawn # 114, Wichita, KS 67208

Company to plug at: Hour: 1:00 am Day: 9 Month: October Year: 19 84

Plugging proposal received from Gary Bagby

(company name) Cougar (phone) 316-456-7259

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 690' with 50 sx cement

2nd plug at 340' with 50 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

6th plug to circulate mouse hole with 10 sx cement.

Plugging Proposal Received by Paul A. Luttie
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 2:15 am Day: 9 Month: October Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 690' with 50 sx cement, 2nd plug at 340' with 50 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with

10 sx cement, 5th plug to circulate rat hole with 15 sx cement, 6th plug to circulate mouse hole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

OCT 12 1984
10-12-84

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun

(If additional description is necessary, use BACK of this form.)

INVOICED

(do not) observe this plugging.

DATE 10-15-84

Signed Paul A. Luttie
(TECHNICIAN)

INV. NO. 4328