

To: 1 041228
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 15-185 10114-00-01 Docket #D-21,477
NW SW NE, SEC. 29, T 23 S, R 12 WXX
3630 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License / 3911
Operator: RAMA Operating Company, Inc.
Name:
Address P.O. Box 159
Stafford, KS 67578

Lease Name Rice Well # 2 OWWO
County Stafford 135.85
Well Total Depth 4180 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 674

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well X D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529
Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 10:45 a.m. Day: 27 Month: 12 Year: 1996

Plugging proposal received from Mike Kelso
(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

Work: 4 1/2" at 3970' w/200 sx cement, Open hole 3970-4180', Junk left in hole-App. 500' of tubing / Tubing fish at 3400', TOC 2760'

- 1st plug sand back to 3350' and dump 4 sx cement on top of sand through bailer,
- 2nd plug at 700' with 50 sx cement,
- 3rd plug at 40' with 10 sx cement.

Plugging Proposal Received by Kevin Strube
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 12 p.m. Day: 27 Month: 12 Year: 1996

ACTUAL PLUGGING REPORT 1st plug sanded back to 3360' and dumped 4 sx cement on top of sand bridge through bailer,

Spotted plugs through 4 1/2" casing: 9-2-97
2nd plug at 710' with 300 lbs. hulls and 50 sx cement,
3rd plug at 120' with 30 sx cement to surface.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2518' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

It is recommended that you observe this plugging.

Signed Stephen J. Pfeifer
(TECHNICIAN)

INVOICED
DATE JAN 06 1997
INV. NO. 47276