

15-185-10941-0000

To: 1 120977  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

9-30

API NUMBER 15- Drilled 8/3/50

NE NW SE, SEC. 29, T 23 S, R 12 W XE  
2310 feet from S section line  
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 3911  
Operator: RAMA Operating Co., Inc.  
Name & Address: P.O. Box 159  
Stafford, KS 67578

Lease Name Rice-Williams Well # 1  
County Stafford  
Well Total Depth 3867 125.67 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 674

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050  
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9:30 a.m. Day: 30 Month: 9 Year: 19 94

Plugging proposal received from Vernon Duntz

(company name) Kelso Casing Pulling (phone) 316-938-2943

work: 5 1/2" at 3862' w/100 sx cement, Open hole  
1st plug sand back to 3810' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release  
8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11 a.m. Day: 30 Month: 9 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3810' and dumped 5 sx cement on  
top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 100 lbs. hulls,  
released 8 5/8" wiper plug and pumped 175 sx cement. Bottom of cement plug at 700'.

Pumping pressure 0-850 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2200' of 5 1/2" casing  
(If additional description is necessary, use BACK of this form.)

RECEIVED  
STATE CORPORATION COMMISSION  
10-4-94 OCT 4 1994  
WICHITA, KANSAS

Signed \_\_\_\_\_  
(TECHNICIAN)

INVOICED

DATE 10-10-94  
INV. NO. 41380