

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-01610-00-01
Spot: SWSWNE Sec/Twnshp/Rge: 29-23S-11W
2970 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: ALLEN E F Well Number: 1
County: STAFFORD Total Vertical Depth: 3667 feet

Operator License No.: 100
Op Name: KANSAS CORPORATION COMMISSION
Address: 130 S MARKET RM 2078
WICHITA, KS 67202

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 295
Production: Size 4.5 feet: 3667 WITH 150 SX CMT
Liner: Size _____ feet:

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/19/2002 3:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: RICHARD LACEY Company: KCC Phone: (620) 225-8888

Proposed Plugging Method: SAND BOTTOM TO 3290' & PLACE 4 SX CMT ON TOP OF SAND WITH DUMP BAILER. FREEPOINT & RECOVER CASING PULLING TO 600'. SPOT 10 SX GEL & 50 SX CMT AT 600'. PULL CASING TO 330' & SPOT 50 SX CMT. PULL CASING TO 40' & SPOT 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 02/19/2002 4:35 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PERFS AT 3407-3447'. SANDED TO 3080' & 4 SX CMT WITH DUMP BAILER. SHOT PIPE AT 2120'. PIPE PARTED AT 1220'. SPOTTED PLUGS THROUGH CASING. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 330' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

RECEIVED
MAR 06 2002
KCC WICHITA

See Joint

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1220' OF 4 1/2" CASING.

Plugged through: CSG

Control #20020015-001

District: 01

Signed Richard M. Lacey
(TECHNICIAN)

FEB 26 2002

Form CP-3/3