

KANSAS

KS STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

OCT 12 1967

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued September 14, 1967.

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Satin Supply Company

Complete Address: 925 National Bank of Tulsa Bldg., Tulsa, Oklahoma 74103

Lease Name Schieb Well No. # 4

Location NW SW NW Sec. 27 Twp. 22 Rge. 12 (E) (W) W

County Stafford Total Depth 3720'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Lynch Casing Pulling Company

Address: R. R. # 4, Great Bend, Kansas 67530 License No. 457

Operation Completed: Hour 10:15AM Day 11th Month October Year 1967

The Above well was plugged as follows:

280' of 8 5/8" surface pipe, cemented with 250 sacks. 3719' of 4 1/2" long string,
cemented with 175 sacks. No record of any perforations. Bottom of the hole was
sanded to the top of the Kansas City at 3300', and cemented with 4 sacks, through
the dump bailer, with cement from 3300' to 3250'. 2728' of 4 1/2" long string was re-
covered from the hole. Bridge plug was pushed in fluid to 260', bridge plug and
rock bridge from 260' to 250'. 8 sacks of cement was mixed in a barrel, and put on
plug at 250', through the dump bailer, and let set over-night. Next day hole was
bailed dry, and 17 sacks of cement was added to the plug. Hole was filled with mud
to 40', rock bridge from 40' to 30', and cemented with 10 sacks, with cement from
30' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED

DATE 10/12/67
INV. NO. 6486-W