

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 9 1967

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued September 14, 1967.

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Satin Supply Company
Complete Address: 925 National Bank of Tulsa Bldg., Tulsa, Oklahoma 74103
Lease Name Schieb Well No. # 3
Location NE SW NW Sec. 27 Twp. 22 Rge. 12 (E) (W) W
County Stafford Total Depth 3750'
Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated: _____
Plugging Contractor: Lynch Casing Pulling Company
Address: R. R. # 4, Great Bend, Kansas 67530 License No. 457
Operation Completed: Hour 10:30AM Day 6th Month October Year 1967

The Above well was plugged as follows:

250' of 8 5/8" surface pipe, cemented with 250 sacks. 3750' of 4 1/2" long string,
cemented with 150 sacks. No record of any perforations. Plug and sand to the top of
the Kansas City at 3300', and cemented with 4 sacks, with cement from 3300' to 3250
2794' of 4 1/2" long string was recovered from the hole. Bridge plug was pushed in
fluid to 250', bridge plug and rock bridge from 250' to 240'. 8 sacks of cement was
mixed in a barrel, and put on plug at 240', through the dump bailer, and let set
over-night. Next day hole was bailed dry, and 17 sacks of cement was added to the
plug, with cement from 240' to 165'. Hole was filled with mud to 40', rock bridge
from 40' to 30', and cemented with 10 sacks, with cement from 30' to the base of
I hereby certify that the above well was plugged as herein stated.
the cellar.

Signed: Annie Elving
Well Plugging Supervisor

INVOICED

DATE 10/9/67
INV. NO. 6464-W