

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 16 1978

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15-185-20764-0000 (of this well)

Operator's Full Name Bergman Oil Co.
Complete Address 520 Union Center, Wichita, Kansas - 67202-
Lease Name Frankenberg Well No. 3
Location SW-NE-SW Sec 27 Twp. 22 Rge. 12 (E) (W) X
County Stafford Total Depth 3548
Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Felsa Casing Plugging
Address Box 176 - Chase, Kansas - 67524 License No. 683

Operation Completed: Hour 12:30 pm Day 12 Month May Year 1978

The above well was plugged as follows:

290'-8 5/8" casing w/200 sack cement - 4 1/2" casing set @ 3646'
w/200 sack cement - prep 3641'-51' sand back to 3600'
top sand w/4 sack mixed cement w/ dump bailer pull
2520' 4 1/2" casing - mix & pump 5 sack hulls - 20 gel release
plug - mix & pump 125 sack 50/50 for mix cement to top
of casing - Shut in w/ 800# pressure - This well was
drilled to 3701' - lost circ bottom of hole - cemented same
Applied Cementing Co. - G. B. Bend, Kansas - 67530

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 5-16-78
INV NO. 7314-U