

KANSAS

W
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

OCT - 2 1967

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued September 14, 1967.

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Satin Supply Company
Complete Address: 925 National Bank of Tulsa Bldg., Tulsa, Oklahoma 74103
Lease Name Schieb Well No. # 2
Location SW SW NW Sec. 27 Twp. 22 Rge. 12 (E) (W) W
County Stafford Total Depth 3740'
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated: _____
Plugging Contractor: Lynch Casing Pulling Company
Address: R. R. # 4, Great Bend, Kansas 67530 License No. 457
Operation Completed: Hour 10:15 AM Day 29th Month Sept. Year 1967

The Above well was plugged as follows:

250' of 8 5/8" surface pipe, cemented with 250 sacks. 3740' of 4 1/2" long string, cemented with 150 sacks. No record of any perforation. Plug and sand to the top of Kansas city at 3300', and cemented with 4 sacks, with cement from 3300' to 3250'. 2385' of 4 1/2" long string was recovered from the hole. Bridge plug was pushed in fluid to 240', bridge plug and rock bridge from 240' to 230'. 4 sacks of cement was mixed in a barrel, and put on plug at 230', through the dump bailer, and let set over-night. Next day hole was bailed dry, and 21 sacks of cement was added to the plug, with cement from 230' to 155'. Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks, with cement from 30' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED

DATE 10/2/67
INV. NO. 6427-11