

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 29 1971
 CONSERVATION DIVISION
 Wichita, Kansas

Operator's Full Name Duke Drlg. Co.
 Complete Address 1105 Williams Great Bend, Ks
 Lease Name Schieb Well No. 1
 Location App. SE/SW/NW Sec. 27 Twp. 22 Rge. 12 (E) (W)
 County Stafford Total Depth 3681
 Abandoned Oil Well Gas Well Input Well SWD Well D & A
 Other well as hereafter indicated _____
 Plugging Contractor Southwest Casing Pulling Co. Inc.
 Address Box 364 Great Bend, Ks License No. 399
 Operation Completed: Hour 10:00 AM Day 27 Month 11 Year 1971

The above well was plugged as follows:

288 ft 8 5/8 surface pipe cemented with 250 sacks. 3678 ft 5 1/2 long
string cemented with 125 sacks. Top perf. 3438 ft. Sand back to
3420 ft, 5 sacks cement with bailer. Pulled 1900 ft 5 1/2. Pump
2 sacks hulls, 15 sacks gel, 100 sacks cement to surface.
Pumped by Sun Cementing Co. Great Bend, Ks

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE

12-1-71

INV. NO.

4710-W

Signed: [Signature]

Well Plugging Supervisor