

Form CP-3  
Rev. 6-26-62

**K**  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

**RECEIVED**  
STATE CORPORATION COMMISSION

MAY 19 1967

CONSERVATION DIVISION  
WICHITA, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Well Plugging Authority,  
issued May 9, 1967.

Operator's Full Name Santa Fe Pipe & Supply, Inc.

Complete Address: P. O. Box 562, Great Bend, Kansas 67530

Lease Name Byers Well No. # 3

Location C S/2 NE NE Sec. 23 Twp. 22 Rge. 12 (E) (W)W

County Stafford Total Depth 3661'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Santa Fe Pipe & Supply, Inc.

Address: P. O. Box 562, Great Bend, Kansas 67530 License No. 574

Operation Completed: Hour 9:30AM Day 16th Month May Year 1967

The Above well was plugged as follows:

283' of 8 5/8" surface pipe, cemented with 165 sacks. 3656' of 5 1/2" long string,  
cemented with 100 sacks. Top perferation 3298'. Bottom of the hole was sanded  
to 3285', and cemented with 5 sacks, through the dump bailer. 2932' of 5 1/2" long  
string was recovered from the hole. Bridge plug was pushed in fluid to 270',  
rock bridge from 270' to 255'. 2 sacks of cement and 10% Calcium Chloride was  
mixed in a barrel, and put on plug at 255', through the dump bailer, and let  
set over-night. Next day hole was bailed dry and 23 sacks of cement was added  
to the plug. Hole was filled with mud to 40', rock bridge from 40' to 30', and  
cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

DATE 5/19/67  
INV. NO. 5248-W

Signed: Audie Elving  
Well Plugging Supervisor