

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 141-40

LOCATION 21.5 21.5-22E

SEC. 23 TWP. 22 RGE. 12-w

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Opal

Operator Musgrove Petro. Corp. Address 407 K.F.H. Bldg. Wichita-Kans.

Field \_\_\_\_\_ County Stafford

Total Depth 3669 Feet.

(Describe briefly the manner in which the well was plugged)

*Surface Pipe 8 1/2" - 211ft Circulated with cement  
5/8" casing set at 3667 ft - 200 sacks of cement  
Dumped 6 sacks of cement on bottom of hole  
Shot off & pulled the 5/8" casing - mud to 210 ft -  
Set rock bridges & 15 sacks of cement at 210 ft -  
Mud to 35 ft - Plug & 10 sacks of cement  
at the surface -  
Layhawk Pipe Pulling Co. - Plugging Contractor*

MAR 1 - 1952  
*C. W. Stoen*  
District Conservation Agent

**PLUGGING**  
FILE SEC 23 TWP 22 RGE 12-w  
PAGE 141 LINE 40

Date 2-28-52