

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-063-21886-00-00
Spot: W2SESENW Sec/Twnshp/Rge: 13-13S-28W
2310 feet from N Section Line, 2208 feet from W Section Line
Lease Name: TUTTLE Well #: 1
County: GOVE Total Vertical Depth: 4413 feet

Operator License No.: 33268
Op Name: RL INVESTMENT, LLC
Address: 217 SAINT PETER ST
MORLAND, KS 67650

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4413		175 SX
SURF	8.625	234		165 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/27/2017 8:30 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: RANDALL PFEIFER Company: RL INVESTMENT, LLC DBA Phone: (785) 421-6448

Proposed Plugging Method: Ordered 425 sx 60/40 pozmix 4% gel cement, 16 sx gel and 600 # hulls.
DV Tool at 2009' w/175 sx cement.
Perforations: 4295' - 4297'

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/27/2017 12:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Perfs:

Ran tubing to 4298' and pumped 16 sx gel followed by 50 sx cement. Pulled tubing to 2100' and pumped 100 sx cement. Pulled tubing to 1200' and pumped 150 sx cement. Good circulation of cement. Pulled tubing out. Topped off casing with 20 sx cement. Tied on to backside and squeezed with 5 sx cement. Shut in pressure 300 psi.


GPS: 38.92455 -100.38288

Remarks: ALLIED CEMENT TICKET # 68268

Plugged through: TBG

District: 04

Signed _____



(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

MAR 13 2017

CONSERVATION DIVISION
WICHITA, KS

FEB 27 2017

Form CP-2/3

MAR 28 2017