

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-055-22228-00-00Spot: SESWNWSec/Twnshp/Rge: 36-22S-31W2979 feet from S Section Line, 4173 feet from E Section LineLease Name: KATHLEEN 2231Well #: 1-36County: FINNEYTotal Vertical Depth: 5223 feetOperator License No.: 34192Op Name: SANDRIDGE EXPLORATION AND PROAddress: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4794		WITH 2 SX CMT
PROD 7		5223	1918	WITH 505 SX CMT
SURF	9.625	1879		WITH 450 SX CMT

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 02/07/2017 1:00 PMPlug Co. License No.: 33338Plug Co. Name: ORR ENTERPRISES, INC.Proposal Rcvd. from: SHAWN SANDERSCompany: SANDRIDGE EXPLORATIONPhone: (405) 429-6002Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING

Plugging Proposal Received By:


WitnessType: COMPLETE (100%)Date/Time Plugging Completed: 02/09/2017 6:00 PMKCC Agent: KEN JEHLIK**Actual Plugging Report:****Perfs:**

CIBP @ 4794' WITH 2 SX CMT. RAN CBL FROM 3300' TO 1660'. FOUND TOC AT 1932'. BLEW CASING COLLAR AT 1918'. 1ST PLUG AT 2100' WITH 100 SX CMT. 2ND PLUG AT 1300' WITH 50 SX CMT. 3RD PLUG AT 650' WITH 50 SX CMT. 4TH PLUG AT 64-4' WITH 30 SX CMT.

Top	Bot	Thru	Comments
4840	4846		
4834	4846		

Remarks: USED CLASS C COMMON CEMENT BY ORR ENTERPRISES.Plugged through: TBGDistrict: 01

Signed



(TECHNICIAN)

RECEIVED
FEB 23 2017
KCC DODGE CITY



INVOICED

MAR 28 2017

Form CP-2/3