

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 266 N. Main St., Ste. 220
 Wichita, KS 67202-1513

API Well Number: 15-057-20800-01-00
 Spot: SENESENE Sec/Twnshp/Rge: 2-27S-22W
4933 feet from S Section Line, 225 feet from E Section Line
 Lease Name: POWERS Well #: 1-2H
 County: FORD Total Vertical Depth: 4947 feet

Operator License No.: 34192
 Op Name: SANDRIDGE EXPLORATION AND PRO
 Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4850		WITH 100 SX CMT
COND	20	100		WITH 10 SX CMT
	11 7	5510	1274	WITH 300 SX CMT
PROD	4.5	9182		WITH 450 SX CMT
SURF	9.625	1225		WITH 510 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/08/2017 3:00 PM
 Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
 Proposal Revd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 4850' WITH 100 SX CMT. PLUG AT 1260' WITH 100 SX CMT. PLUG AT 750' WITH 50 SX CMT. PLUG AT 60' WITH 30 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: PARTIAL
 Date/Time Plugging Completed: 03/08/2017 5:00 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

3/7/17: SET CIBP @ 4850'. CIRCULATE HOLE WITH 180 BBLs MUD & CAP WITH 100 SX CMT. PULL TBG TO 3000'. 3/8/17: 1ST PLUG AT 1260' WITH 100 SX CMT. 2ND PLUG AT 750' WITH 50 SX CMT. 3RD PLUG AT 64'-4" WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
8160	8567		
7667	8063		
7178	7580		
6673	7077		
6187	6583		
5708	6107		
5220	5632		

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY ORR ENTERPRISES. TMD= 9182'

Plugged through: TBG

District: 01

RECEIVED
 MAR 16 2017
 KCC DODGE CITY



Signed: [Signature]
 (TECHNICAL)

51A

MAR 28 2017