

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-077-21952-00-00  
Spot: E2W2NWNW Sec/Twnshp/Rge: 23-33S-6W  
660 feet from N Section Line, 560 feet from W Section Line  
Lease Name: ALTON 3306 Well #: 1-23  
County: HARPER Total Vertical Depth: 4920 feet

Operator License No.: 34192  
Op Name: SANDRIDGE EXPLORATION AND PRO  
Address: 123 ROBERT S. KERR AVE  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4907		330 SX
SURF	8.63	630		340 SX
T1	2.875	4751		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/01/2017 8:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (405) 429-6002

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL  
Date/Time Plugging Completed: 03/01/2017 6:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

ESP STUCK IN HOLE. CUT TUBING @ 4300', TUBING STUCK IN HOLE. TUBING ON VACCUM. PUMPED 50 SX CEMENT AND 25# HULLS DOWN TUBING. DISPLACED TO 4250' & SHUT DOWN FOR WEEKEND. ON MONDAY WE PUMPED DOWN TUBING & PRESSURED TO 1500#. PERF'D TUBING & CASING AT 1800', ANNULAS CIRCULATED. PUMP 50 SX CEMENT. PERF'D T & C AT 1150' & PUMPED 50 SX CEMENT. TUBING FREE POINT AT 890'. CUT & PULLED TUBING FROM 890'. FREE POINT CASING AT 824'. CUT & PULLED CASING FROM 824'. RAN TUBING BACK IN HOLE TO 680' & SPOTTED 50 SX CEMENT. PULLED TUBING TO 300' & CIRCULATED CEMENT TO SURFACE WITH 100 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
4662	4674		
4413	4423		

Remarks: ORR ENTERPRISES, CLASS C CEMENT.

Plugged through: TBG

District: 02

Signed  (TECHNICIAN)

INVOICED  
MAR 28 2017

1/2