

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-071-20609-00-00
Spot: W2E2NENW Sec/Twnshp/Rge: 2-18S-43W
4703 feet from S Section Line, 3190 feet from E Section Line
Lease Name: MOORE-JOHNSON UNIT - WIT Well #: 1
County: GREELEY Total Vertical Depth: 5230 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>5030</u>	DVT		2198		WITH 300 SX CMT
Op Name: <u>VESS OIL CORPORATION</u>	PROD	5.5	5230	0	WITH 150 SX CMT
Address: <u>1700 WATERFRONT PKWY BLDG 500</u> <u>WICHITA, KS 67206</u>	SURF	8.625	362		WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/13/2017 9:00 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: GARRY BROWN Company: _____ Phone: _____

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/14/2017 12:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

3/13/17: DRILL OUT CIBP @ 5075' (OPERATOR REQUEST). PUMP 50 SX CLASS C COMMON WITH 200# HULLS AT 5115'. PARTIAL CIRCULATION. WAIT 2 HOURS & ATTEMPT TO TAG PLUG WITH TBG. RAN TO 5115'. DID NOT TAG CMT. SPOT 50 SX CLASS C COMMON WITH 150# HULLS & 25 BALL SEALERS AT 4500'. SPOT 75 SX CMT WITH 250# HULLS AT 2200' TO SHUT OFF CASING LEAK. SDON. 3/14/17: TAG TOC IN 5 1/2" CASING AT 2198'. RUN TBG TO 2169' & SPOT 50 SX CLASS C COMMON WITH 2% CC & 200# HULLS. FULL CIRCULATION. PULL TBG TO 1500' & CIRCULATE CMT TO SURFACE WITH 130 SX 60/40 POZMIX 4% GEL. TOP OFF WITH 20 SX CMT. PUMP 5 SX CMT DOWN THE ANNULUS TO 200 PSI.

Perfs:


Top	Bot	Thru	Comments
5122	5130		

Remarks: USED CLASS C COMMON & 60/40 POZMIX 4% GEL BY BASIC.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED
MAR 16 2017
KCC DODGE CITY

INVOICED
MAR 28 2017

Form CP-2/3