

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-23489-00-00
Spot: S2SWSW Sec/Twnshp/Rge: 13-34S-11W
334 feet from S Section Line, 4663 feet from E Section Line
Lease Name: D. MEYER Well #: 3-13
County: BARBER Total Vertical Depth: 4826 feet

Operator License No.: 5822
Op Name: VAL ENERGY, INC.
Address: 125 N MARKET ST STE 1110
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4600		WITH 2 SX CMT
PROD	5.5	4826	3850	WITH 100 SX CMT
SURF	8.625	207		WITH 190 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/10/2017 10:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: CIBP @ 4600' WITH 2 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 250' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/10/2017 12:15 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

Perfs:

SET CIBP @ 4600' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 620' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 240' WITH 50 SX CMT. 3RD PLUG AT 42' WITH 30 SX CMT.

Top	Bot	Thru	Comments
4681	4685		

Remarks: USED 60/40 POZMIX 4% GEL BYU QUALITY.

Plugged through: CSG

District: 01

Signed Steve Pfeifer
(TECHNICIAN)

RECEIVED
MAR 13 2017
KCC DODGE CITY

Form CP-2/3

INVOICED
MAR 20 2017