

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-007-23416-00-00  
Spot: NENENE Sec/Twnshp/Rgc: 32-34S-11W  
4961 feet from S Section Line, 557 feet from E Section Line  
Lease Name: ROSE TRUST Well #: 2-32  
County: BARBER Total Vertical Depth: 4900 feet

Operator License No.: <u>5822</u>	String	Size	Depth (ft)	Pulled (ft)	Comments
Op Name: <u>VAL ENERGY, INC.</u>	CIBP		4715		WITH 2 SX CMT
Address: <u>125 N MARKET ST STE 1110</u>	PROD	5.5	4896	3830	WITH 125 SX CMT
<u>WICHITA, KS 67202</u>	SURF	8.625	727		WITH 350 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/08/2017 1:45 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: CIBP @ 4715' WITH 2 SX CMT. PLUG AT 760' WITH 10 SX GEL & 50 SX CMT. PLUG AT 300' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/08/2017 2:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4715' WITH 2 SX CMT. 1ST PLUG PLUG AT 760' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4800	4802		
4784	4792		
4780	4782		
4772	4775		
4762	4802		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed

  
(TECHNICIAN)

RECEIVED  
MAR 13 2017  
KCC DODGE CITY

Form CP-2/3

INVOICED  
MAR 28 2017