

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-073-01719-00-00
Spot: NESESWSW Sec/Twnshp/Rge: 7-22S-12E
400 feet from S Section Line, 4130 feet from E Section Line
Lease Name: CURTIS Well #: 3
County: GREENWOOD Total Vertical Depth: 1788 feet

Operator License No.: 4529
Op Name: HUBER OIL COMPANY, A GENERAL P
Address: 3744 X RD
MADISON, KS 66860

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	1748		0 SX
SURF	10	102		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/17/2017 9:00 AM
Plug Co. License No.: 33413 Plug Co. Name: TITUS WELL SERVICE LLC
Proposal Rcvd. from: EDWARD T. HUBER Company: _____ Phone: (620) 437-6021

Proposed Plugging Method: Perforate with 1 shot at the top of the Douglas and at 250 feet from surface. Place 50 feet of concrete in bottom of hole, then gel spacer, put 50 feet of concrete over Douglas and perforation, then gel spacer, concrete 250 feet to surface. I can find no cementing records.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: NONE
Date/Time Plugging Completed: 02/17/2017 12:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report: ran tubing to 1735', pumped 20 sxs cement, pulled tubing to 900', pumped 20 sxs cement, pulled tubing to 250', pumped 280 sxs cement to surface, gel spacers between cement plugs.

Perfs:
KCC WICHITA
MAR 06 2017
RECEIVED

RECEIVED
KCC DIST #3
FEB 27 2017
CHANUTE, KS
mt

Remarks:
Plugged through: TBG

District: 03 Signed Miko Delfino (TECHNICIAN)

KCC WICHITA
MAR 06 2017
RECEIVED

INVOICED
MAR 28 2017

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report
 Ticket No. **3168**
 Foreman KEVIN MCCOY
 Camp EUREKA

API # 15-073-01719-00-00

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
2-17-17	1233	CURTIS # 3	7	225	12E	GW	Ks
Customer			Unit #	Driver	Unit #	Driver	
Huber Oil Company			105	DAVE G.			
Mailing Address			112	KEVIN M.			
3744 X Rd			114	KEVIN M.			
City			120 P.U.	GARY M.			
Madison							
State		Zip Code					
Ks		66860					

Job Type P.T.A. Hole Depth _____ Slurry Vol. 76 BBL Tubing _____
 Casing Depth 1748' Hole Size _____ Slurry Wt. _____ Drill Pipe _____
 Casing Size & Wt. 5 1/2 Cement Left in Casing _____ Water Gal/SK _____ Other _____
 Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: SAFETY MEETING: 5 1/2 PERFORATED @ 900' & 250'. RAN 2 3/8" TUBING INSIDE 5 1/2 CASING
Spot Cement Plugs AS Following.

20 SKS @ 1735'
Gel SPACER w/ HULLS
20 SKS @ 900'
Gel SPACER
280 SKS 250' to SURFACE

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C 105	1	Pump Charge	750.00	750.00
C 107	30	Mileage	3.95	118.50
C 203	320 SKS	60/40 Pozmix Cement	12.75	4080.00
C 206	1100 *	Gel 4%	.20 *	220.00
C 206	500 *	Gel SPACER	.20 *	100.00
C 214	40 *	HULLS	.45 *	18.00
C 10A	13.76 TONS	TON Mileage	m/c	345.00
KCC WICHITA				
MAR 06 2017				
RECEIVED				
			Sub Total	5631.50
			Less 5%	302.69
			7.5% Sales Tax	422.36

Authorization Witnessed By Ed Huber Title _____ Total **5751.17**

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.