

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-073-23370-00-01

Spot: SEWNNE

Sec/Twnshp/Rge: 23-26S-9E

4112 feet from S Section Line, 1979 feet from E Section Line

Lease Name: JACKSON

Well #: 7

County: GREENWOOD

Total Vertical Depth: 2255 feet

Operator License No.: 35431

Op Name: M & S ENERGY, LLC

Address: 403 VILLAGE RD
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2245		
SURF	8.625	218		

Well Type: EOR

UIC Docket No: E21812.2

Date/Time to Plug: 03/07/2017 9:00 AM

Plug Co. License No.: 7719

Plug Co. Name: CHEEVER WELL SERVICE, INC.

Proposal Rcvd. from: MCLELLEAND OIL

Company:

Phone: (316) 320-9441

Proposed Plugging Method: CIRC CMT TO SURF INSIDE & OUTSIDE HOLE

Plugging Proposal Received By: MICHAEL HEFFERN

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 03/07/2017 1:00 PM

KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Perfs:

ran tubing to 1700' pumped 25 sxs cement, pulled tubing to 1200' pumped 10 sxs cement, pulled tubing to 250', pumped 50 sxs cement, ran 1" down backside of 4.4" to 260' pumped 80 sxs cement to surface, gel spacers between cement plugs, casing shot @ 1200' & 250',

Received
KANSAS CORPORATION COMMISSION
MAR 16 2017
CONSERVATION DIVISION
WICHITA, KS

RECEIVED
KCC DIST # 3
MAR 13 2017
CHANUTE, KS

MH

Remarks:

Plugged through: TBG

District: 03

Signed Mike Heffern
(TECHNICIAN)

INVOICED Form CP-2/3
MAR 28 2017



CONSOLIDATED
Oil Well Services, LLC

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT CEMENT

TICKET NUMBER 52076
LOCATION El Dorado
FOREMAN Fuzzy

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
3-7-17	5436	Jackson #9	22	265	9E	Groverland
CUSTOMER M+S Services LLC / McElanor						
MAILING ADDRESS 2600 N. Chase						
CITY El Dorado	STATE KS	ZIP CODE 67042	TRUCK #	DRIVER	TRUCK #	DRIVER
			603	Tracey		
			667	Jeremy		
			692	Mark		
			866	Fuzzy		

JOB TYPE <u>AWP</u>	HOLE SIZE _____	HOLE DEPTH <u>1700'</u>	CASING SIZE & WEIGHT <u>4 1/2</u>
CASING DEPTH <u>1700'</u>	DRILL PIPE _____	TUBING <u>2 3/8</u>	OTHER _____
SLURRY WEIGHT _____	SLURRY VOL _____	WATER gal/sk _____	CEMENT LEFT IN CASING _____
DISPLACEMENT _____	DISPLACEMENT PSI _____	MIX PSI _____	RATE _____

REMARKS: safety meeting on location. Rig up and attempt to wash plug down to 1900'. Unsuccessful. The 1696 mix 255Ks 60/40 490sel 490cc w/hulls. Pull plug to 1200' mix 105Ks cement w. 490cc hulls, Pull plug to 250' and circulate cement from 250' to surface down 4 1/2 casing and 4 1/2 tubing side with 505Ks cement w/hulls. Side would not circulate - ran 260' 1" pipe and cemented to surface with 805Ks cement. Top of 4 1/2 casing and side with 255Ks. 1605Ks Total 60/40 490sel

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
660451	1	PUMP CHARGE	1900 ⁰⁰	1900 ⁰⁰
660002	30	MILEAGE	715	21450
660711	8.2 Ton.	Tow Mileage Delivery (min)	660 ⁰⁰	660 ⁰⁰
660853	7 hrs.	80 B&L One Truck	100 ⁰⁰	700 ⁰⁰
6606159	300 gal	City water	102	60 ⁰⁰
660829	190 gks	60/40 pos 490	16 ⁰⁰	3040 ⁰⁰
660325	250 #	Calcium chloride	125	31250
660850	40 #	Carbonated hulls	150	20 ⁰⁰
		Subtotal		6907 ⁰⁰
		discount		310815
		Subtotal		379885
		Received KANSAS CORPORATION COMMISSION MAR 16 2017 CONSERVATION DIVISION WICHITA, KS		
		SALES TAX		
		ESTIMATED TOTAL		

AUTHORIZATION _____ TITLE _____ DATE _____

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.