

1 010264

15-185-20710-0001

JUN 25 1987

API NUMBER 15- Docket #D-19,743

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW, SEC. 27, T 22 S, R 12 W/E

4950-2310 feet from S section line

330 2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5339

Lease Name Krankenberg Well #2

Operator: Bergman Oil Company
Name & Address: 520 Union Center Building
Wichita, KS 67202

County: Stafford 123.50

Well Total Depth 3800 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 302

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing License Number _____

Address Box 31, Russell, KS 67665

Company to plug at: Hour: 2:50 p.m. Day: 25 Month: 6 Year: 1987

Plugging proposal received from Lloyd Davis

(company name) Allied Cementing (phone) 913-483-2627

were: 4 1/2" at 3800' Open hole 3800-3900'

1st plug pump 150 sx cement and 1 sx hulls down 4 1/2",

2nd plug pump 100 sx cement down 8 5/8".

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:35 p.m. Day: 25 Month: 6 Year: 1987

ACTUAL PLUGGING REPORT 1st plug ran tubing to 1550' - mixed 1 sx hulls, 5 sx cement,

2nd plug pulled 3 joints - ran 50 sx cement,

3rd plug pulled to 760' - pumped 50 sx cement-circulated, 6-30-87

4th plug tied to back side-pumped 70 sx cement - got 100 lbs. pressure, RECEIVED

5th plug pumped 70 sx cement down 4 1/2" - Pressure to 100 lbs. STATE CORPORATION COMMISSION

Maximum pressure 100 psi and shut in 0 psi. JUN 30 1987

Remarks: Used ATL by Allied. No recovery. CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

INVOICED

Observe this plugging.

DATE 7-1-87

Signed Jacob P. Smith (TECHNICIAN)

INV. NO. 17379