

To: 1 052030

API NUMBER 15-Docket #D-21,100 15-185-21017-0001

STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

12-5
App. NE NW SE, SEC. 27, T 22 S, R 12 W XX

2340 feet from S section line
1615 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6039
Operator: L.D. Drilling, Inc.
Name & Address: Rt. 1, Box 183-B
Great Bend, KS 67530

Lease Name Krey Well # 1
County Stafford 125.58
Well Total Depth 3864 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 275

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well X O&A _____
Other well as hereinafter indicated _____

Plugging Contractor D S & W Well Servicing, Inc. License Number 6901
Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 9 a.m. Day: 5 Month: 12 Year: 19 96

Plugging proposal received from Kent Strube
(company name) D S & W Well Servicing, Inc. (phone) 316-587-3361

was: 4 1/2" at 3720' w/200 sx cement. Open hole 3720-3864'
1st plug sand back to 3670' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 165
sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 10:30 a.m. Day: 5 Month: 12 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded back to 3670' and dumped 4 sx cement on top of sand
through bailer,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.
hulls, and 165 sx cement. 12-9-96

Maximum pressure 500 psi and shut in 400 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1873' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

observe this plugging.

Signed Richard W. Lacey (TECHNICIAN)

INVOICED
DATE DEC 12 1996
INV. NO. 47165