

1 080313

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,163-0000

NW NW NE, SEC. 27, T 22 S, R 12 W/E XX

4950 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8625

Lease Name Scheib Well # 3A

Operator: VAC Petroleum Co.

County Stafford 121.07

Name & Address 333 North Rock Road, Suite 105

Well Total Depth 3725 feet

Wichita, KS 67206

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 263 ✓

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Aldebaran Drilling Co. License Number 5829

Address Box 18611, Wichita, KS 67207

Company to plug at: Hour: 5:00 pm Day: 21 Month: January Year: 19 85

Plugging proposal received from Mark Guinn

(company name) Aldebaran (phone) 316-685-5372

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 3700' with 40 sx cement

2nd plug at 700' with 50 sx cement

3rd plug at 310' with 50 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by J. H. Metz

(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 7:00 pm Day: 21 Month: January Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 3700' with 40 sx cement, 2nd plug at 700' with 50 sx cement, 3rd plug at 310' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole with 10 sx cement.

STATE CORPORATION COMMISSION 1-23-85

JAN 23 1985

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc

(if additional description is necessary, use BACK of this form.)

I (did/did not) observe this plugging.

Signed

J. H. Metz
(TECHNICIAN)

INV. NO. 6743